
NOTES:

- 1 INSTALL STATE SEAL AND DATA PLATE 12" A.F.F. IN LOCATION SHOWN.
- 2 (2) 2×4 COLUMN W/ SIMPSON 1 1/2" WIDE 18 GA. STRAP W/ (6) 10d NAILS TOP AND BOTTOM WHERE SHOWN. 3: INSTALL LEVER ENTRY LOCKSET, DEAD BOLT (KEYED EXTERIOR/THUMBTURH INTERIOR), 10"x 10" WINDOWS (SAFTY GLASS) IN DOOR AND CLOERS



FLOOR PLAN

DOOR SCHEDULE								
MARK	SIZE	DISCRIPTION	HARDWARE					
Α	36 × 80	MD-300	SEE NOTE 3					
			•					

-	MINDHM	SCH	IE L	JULE				
	MARK	SIZE			DISCRIPTION			
	1	30	×	42	CLEAR	INSUL	ATED	GLASS
						LOW	″E″	

TEXAS OF SHELTERS GENERAL

FLOOR PLAN

070407

JOB NO.

NONE


SCALE:


 $\frac{16}{0}$


CLASSROOM


CUSTOMER: PROJECT: 24

Serving The Southwest "Exclusively Though Independent Dealers"









24' x 30' CISD CLASSROOM

SPECIFICATIONS

BOX SIZE:

24' x 30'

TYPE:

GABLE

FLOOR:

BOTTOM BOARD:

ROLL

INSULATION:

R11 KRAFT

JOISTS:

2x8 @ 16" O.C. (#3 SYP)

DECKING:

3/4" STURDI FLOOR T&G PLYWOOD

COVERING:

1/8 TILE

SKID:

P/T LAMINATED (3 LAYER)

EXTERIOR WALLS:

STUDS:

2x4 STUD GRADE @ 16" O.C. - 8'-0" WALL HT.

BOTTOM PLATE: TOP PLATE:

2x4 SINGLE BOTTOM PLATE 2x4 DOUBLE TOP PLATE

COVERING:

1/2" VINYL COVERED GYPSUM W/ 4" BASE

SHEATHING:

3/8" OSB RII KRAFT

INSULATION: SIDING:

26 Ga. PAINTED GALVANIZED STEEL (0.0217 NOM.)

TRIM:

26 Ga. PAINTED GALVANIZED STEEL (0.0217 NOM.)

INTERIOR WALLS:

STUDS:

COVERING: NONE NONF INSULATION:

CLOSETS:

NONE

NONE

NONE

ROOF:

RAFTERS:

2X8 (#3) SYP 16" O.C.

CEILING JOIST:

MATE BEAM:

ENGINEERED GIRDER

CEILING:

SUSPENDED "T" BAR R-19 KRAFT FACED FIBERGLASS

INSULATION:

1/2" CDX PLYWOOD SHEATHING

SHFATHING:

ROOFING:

26 Ga. PAINTED GALVANIZED STEEL (0.0217 NOM.)

TRIM:

26 Ga. PAINTED GALVANIZED STEEL (0.0217 NOM.)

TIE DOWN:

(4) OVER THE ROOF (PER SIDE)

DOORS:

EXTERIOR DOORS:

(2) 36" x 80" MD-300, 10X10 WINDOW

LEVER & KEYED LOCK/DEADBOLT & CLOSER

INTERIOR DOORS:

NONE

WINDOWS:

WINDOW 1:

(2) 30x42 INSULATED CLEAR GLASS, V/S, LOW "E"

ELECTRICAL:

LOAD PANEL:

(1) 125-AMP W/MAIN ("A" SIDE)

(1) 125-AMP MAIN LUG ONLY ("B" SIDE)

RACEWAY:

EMT (#12 WIRE MINIMUM)

LIGHTS:

(9) FLUORESCENT (2) BULB 4' DROP-IN

(2) PORCH LIGHTS (PHOTOCELL)

RECEPTACLES:

(7) 110-VOLT 15-AMP DUPLEX

(1) 110-VOLT 15-AMP GFI DUPLEX

MISCELLANEOUS

(2) EMERGENCY/EXIT LIGHT

PLUMBING:

WATER CLOSETS:

NONE MODESTY PARTITION: NONE

URINAL:

NONE NONE

LAVATORY: WATER HEATER:

NONE

SHOWER:

NONE

POTABLE WATER:

NONE

DWV:

NONE NONE

SEWER VENT: ACCESSORIES:

NONE

MISCELLANEOUS:

NONE

HVAC:

A/C - HEATING:

PER ENGINEERED CALCS. (3 TON)

DUCT:

FIBERGLASS

DIFFUSERS:

(6) 2' x 2' 4-WAY (DROP-IN)

RFTURNS:

AT UNIT

EXHAUST FANS:

NONE

MISC:

COFFEE BAR:

NONE

MISC.:

NONE

GENERAL SHELTERS OF TEXAS, INC.

24 x 30



"Exclusively Though Independent Dealers"

TITLE: **SPECIFICATIONS**

CUSTOMER:

PROJECT:

CLASSROOM

JOB NO.

070407

SHFFT

7/16/07 DATF:

SCALE: NONF